

Grasmere Town Hall Septic System – Addendum #2: 10/11/16

1) The piping from the pump chamber to the leach field shall be Schedule 40 PVC pipe (was originally specified as galvanized pipe)