

2014 East Dunbarton Rd. Reclamation Project
East Dunbarton Road
Goffstown, NH
Addendum 1 - Bidder's Questions/Answers
Issued 12/6/2013

Below is a list of questions that have been received by the Goffstown Department of Public Works regarding the 2014 Road Reclamation Project for East Dunbarton Road that is currently out to bid. In an attempt to keep all bidders on the same page, we are issuing this addendum which answers the bidder questions that have been received.

Question 1 - Will the contractor be responsible for establishing crushed gravel shoulders once pavement is placed?

Answer - The Contractor will be responsible for establishing crushed gravel shoulders after base and top course pavement has been placed. Quantity for crushed gravel shoulder is included in bid item.

Question 2 - Will the contractor be responsible for rough grading reclaim and crushed gravel material?

Answer - As stated in Measurement and Payment section 01025 the contractor will be responsible for proper rough grading of all layers to a 3% crown (subgrade, reclaim, and crushed gravel). Work being coordinated by OWNER and done BY OTHERS is pulverizing the existing pavement to a min. depth of 10 inches, installation of the base and wearing courses of pavement and installation of bituminous curbing.

Question 3 - Does the contractor need to post flaggers at the end of each detour if it is decided that the road can be closed?

Answer - Flaggers will not need to be posted on the end of each detour if the road is closed. Please see Measurement and Payment Section 01025 under bid item Maintenance of Traffic for more detail. The contractor **shall** submit a Traffic Control Plan and Device Package, meeting the requirements and standards of the latest edition of the MUTCD, Goffstown Police Chief, Engineer, and Owner and shall receive approval for the plan prior to beginning construction.

Question 4 - Will the contractor be responsible for road layout and staking related to reclaim and crushed gravel placement?

Answer - The contractor will be responsible for all road layout and staking related to reclaim and crushed gravel. This will be incidental to the cost of crushed gravel and reclaim.

Question 5 - How will pre-blast surveys paid for?

Answer - Pre-blast surveys are incidental to Trench Rock Excavation. See Blasting and Explosives Section 01540 and Measurement and Payment Section 01025 for more detail.