

Town of Goffstown
Parks and Recreation Department
Roy Park Playground

INVITATION TO BID:

The Goffstown Parks and Recreation Dept. invites bids from qualified suppliers and installers of playground equipment for Roy Park, 31 Rosemont Ave., Manchester, NH 03012. Sealed bids will be received at the Administration Office, 16 Main St., Goffstown, NH 03045 until 3:30 pm Friday April 15, 2016 at which time the bids will be publicly opened and read. All bid proposals must be submitted in a sealed envelope, clearly marked on the outside with "2016 Roy Park Playground". The Town reserves the right to reject and/or waive any bids or parts of bids if deemed in the best interest of the Town.

PLAYGROUND EQUIPMENT:

The Town will not except materials preserved, coated or treated with chemicals such as Arsenic, Lead, PVC chemicals, Creosote, Pentachlorophenol, or similar chemicals or preservatives. The Town is requiring environmentally sound equipment and resilient surfacing, both compliance with current published ASTM standards, and USCPSC Playground Safety Guidelines and ADA Play Area Design Standards. The total design area will be 71' x 90' or 6,390 square feet. Please give cost per item.

Item # 1 – Age Group 5 – 12 years

A tree house type of structure with minimum of 13 activity stations, fall height of 9', user zone of 50' x 37', made of conditioned wood with galvanized steel footings.

Cost: \$ _____

Item #2 – Age Group 2 – 5 years

A tree house type of structure with a minimum of 13 activity stations, fall height of 4' 6", user zone of 24' x 25', made of conditioned wood with galvanized steel footings.

Cost: \$ _____

Item #3 – 8' height / 4 bay Swing set

To include: bay 1 – two bucket seats, bay 2 – two belt seats, bay 3 – two belt seats, bay 4 – one belt, one ADA seat. Made of 6" OD steel post.

Cost: \$ _____

Item #4 & #5 – (2) Self powered sensory development (one over head/ one ground level) merry go round activity

- 1 – User zone of 17' diameter, fall height 5'2"
- 2 – User zone of 18' diameter, fall height 5'2"

Cost: \$ _____

Item #6 – Multi rider teeter totter / overhead activity

User zone of 25' 6" x 16" 10", fall height of 7' 8"

Cost: \$ _____

Item #7 Climbing / crawling / tunnel type of activity – group of 3 plastic tubes.

User zone of 24' x 18', fall height of 3'5"

Cost: \$ _____

TOTAL EQUIPMENT COST: \$ _____

PROJECT MATERIAL:

Playground area will be 71' x 90' or 6,390 square feet

- Stone – Clean rock 3" deep 6,390 sf. Cost (delivered): \$ _____
- Drainage Fabric
 - One layer Cost (delivered): \$ _____
 - Two layers Cost (delivered): \$ _____
- Wood Retaining Timers – ACQ Preserve or equal – Top timber to be routed/curfed - No Arsenic.
 - Two tiers or 324 linear feet x 2, rebar and screws Cost (delivered): \$ _____
- Engineered Wood fiber – 12" compacted depth (320 yards)
 - Based on 6,390 square feet Cost: \$ _____
 - Based on 6,390 square feet Cost (delivered): \$ _____
- Rubber tiles with beveled edges – under belt swings – ends of slides
 - 4' x 6' x 2" thick Cost (delivered): \$ _____

TOTAL MATERIAL COST: \$ _____

INSTALLATION:

Playground Equipment / Surfacing:

A final site plan will identify the placement of all activity stations to be installed in designated location. Contractor will schedule off load of all material on site or have delivered to third party location and take full responsibility of product.

Playground equipment (Activity Stations):

Contractor will supply material to install each activity station as so it meets all manufactures guidelines and meet all USCPCS Playground Safety Guidelines. Cost: \$ _____

Surfacing:

Contractor will fill area (6,370 SF) and compact with trap rock material (dirty stone) to a depth of 15" below the final grade. Place a layer of drainage fabric, then 3" of stone (clean rock ¾" to 1"), Place second layer of drainage fabric. Install two tier retaining timbers. Wood fiber and drainage stone installed after equipment.

Cost: \$ _____

TOTAL INSTALLATION COST: \$ _____

GENERAL BID REQUIREMENTS:

Insurance:

In compliance with RSA 447:16 a performance bond is required of the successful vendor for all projects in excess of \$35,000, such bond shall equal the total project cost. Successful vendor will show proof of liability insurance in the amount of \$1,000,000 with the town named as an additional insured, and workers compensations insurance or in the case of a sole proprietor an Independent Contractor Work Agreement (see Attachment B in Town of Goffstown Purchasing Policy)

Evaluation Criteria:

Bids will be evaluated based upon: (1) price; (2) ability to meet all bid specifications; (3) references

General Bid Information:

Bids, when opened, shall be irrevocable for a period of sixty (60) calendar days following the bid opening date. Following a review of all bids by the Parks & Recreation Director, a recommendation will be sent to the Board of Selectmen for a bid award.

Any questions regarding these bid specifications should be directed to Parks & Recreation Director Rick Wilhelmi at (603) 497-8990 Ext. 401 or email rwilhelmi@goffstownnh.gov.

Signatures:

The undersigned certifies under penalties of perjury that this bid is in all respects bonafide, fair and made without collusion or fraud with any other person. As used in this section the word "person" means any natural person, joint venture, partnership, corporation or other business or legal entity.

(Name of person signing bid)

(Company Name)

(Date)